

# **Anacostia Flood Risk Reduction**

## **Levee Rehabilitation Case Study**

**Maureen P. Cissel, CFM**

# Discussion Topics

- **Levee System Overview**
- **Evaluate Existing Conditions**
- **Plan Improvements**
- **Complete Rehabilitation**
- **Provide Sustainability**
- **Looking Forward**

# 1 **LEVEE SYSTEM OVERVIEW**


---



# Anacostia Levee System

**Constructed in the 1950s, the levee includes:**

- **More than five miles of earthen levees**
- **Twin 8x4 pressure conduits 2500 feet long**
- **Four flood control pumping stations**
- **Gravity outfall**



# Ongoing Investment in Levee System

- **Construction of new screw pumps**
- **Replacement of flapper valves**
- **Installation of automatic bar screen cleaners**
- **Emergency generator installations at each pumping station**
  
- **No levee failures, overtopping or breaches**
- **Engaged in H&H Analysis**

**Levee owner was advised that the levee system would not meet the standards for FEMA accreditation.**


**What does that mean?**

# 2 EVALUATE EXISTING CONDITIONS





- **Field Inspection**
  - **Penetrations**
  - **Structures**
  
- **Concrete Testing**
  
- **Utility Coordination**
  
- **Review of Historical Records**







C2-COREA-S2



← TOP




## Subsurface Investigation



# Concept Design Report

- **Summarized alternatives**
- **Cost Benefit Analysis**
- **Property and community impacts**

# Typical Section





# 3 **PLANNING**

---



# Stakeholders Outreach

- **Public Outreach**
- **Elected Officials**
- **Property Owners**
- **Maintenance Division**

## Outreach Methods

- **Briefings to elected officials**
- **Community meetings, press releases and website updates**

# 4 **COMPLETE REHABILITATION**


---




## **4 Separate Contracts to Address Deficiencies**



- **Levee Rehabilitation**
- **Flood Control Pumping Stations Repair and Upgrades**
- **Pressure Conduit Access Vaults, Cleaning and Evaluation**
- **Steep Slope Improvements to allow for Maintenance**
























# 5 **SUSTAINABILITY**

---





# Edmonston-Bladensburg Flood Protection System

Operation & Maintenance Manual

May 2013



Bladensburg Stormwater Pumping Station  
4601 Annapolis Road  
Bladensburg, MD 20710

# Colmar Manor Stormwater Pumping Station

Operation & Maintenance Manual


October 2011



# Edmonston Stormwater Pumping Station

Operation & Maintenance Manual

2010




4923 Taylor Road, Riverdale, MD 20737

## EMERGENCY ACTION PLAN (EAP)

### BRENTWOOD LEVEE SYSTEM Anacostia River

Brentwood Flood Control Pumping Station  
4018 Banner Street  
Prince George's County, Maryland



Reviewed and Updated:

Date \_\_\_\_\_


Levee Sponsor  
Director of Prince George's County Department of Public Works and Transportation

Copy \_\_\_\_ of \_\_\_\_

## EMERGENCY ACTION PLAN (EAP)

### EDMONSTON – BLADENSBURG LEVEE Anacostia River Levee System

Bladensburg Flood Control Pumping Station  
4601 Annapolis Road  
Prince George's County, Maryland



Reviewed and Updated:

Date \_\_\_\_\_


Levee Sponsor  
Director of Prince George's County Department of Public Works and Transportation

Copy \_\_\_\_ of \_\_\_\_

## EMERGENCY ACTION PLAN (EAP)

### COLMAR MANOR LEVEE SYSTEM Anacostia River

Colmar Manor Flood Control Pumping Station  
4327 Monroe Street  
Prince George's County, Maryland



Reviewed and Updated:


Date \_\_\_\_\_

Levee Sponsor  
Director of Prince George's County Department of Public Works and Transportation

Copy \_\_\_\_ of \_\_\_\_

## Checklists were developed:

- **Maintenance Personnel**
- **Electrical and Mechanical Contractor(s)**



**ELECTRICAL AND MECHANICAL MAINTENANCE OF FLOOD CONTROL ANNUAL TESTING REQUIREMENTS**

Pumping Station: \_\_\_\_\_ Date: \_\_\_\_\_ Company: \_\_\_\_\_ Signature: \_\_\_\_\_

Interior Electrical System			
7.1	Front Switch & Water Level Indicator Assemblies	1	
7.1.1	Front	1	
7.1.2	Perform Dial Calibration	1	
7.2	Lighting Fixtures (Interior and Floodlights) - lamps, ballasts, lenses, and similar items. Check for Proper Operation.	1	
7.3	Emergency lighting units and exit lighting fixtures - lamps, battery condition, test circuit, indicators. Check for Proper Operation.	1	
7.4	Dehumidifier Motor & Circuit and drain line	1	
7.5	Heater Circuit and Breaker and operation of Thermostat	1	
7.6	Roof Ventilators, Louvers, Dampers and associated circuits; check operation and interlocking.	1	
7.7	Wall Switches, Receptacles, and Covers	1	
7.8	Cellular Phone Switch	1	

**MONTHLY INSPECTION REPORT**

Pumping Station: \_\_\_\_\_ Date: \_\_\_\_\_ Company: \_\_\_\_\_ Signature: \_\_\_\_\_

Item	Applicable Station	Condition	Recommended Repair
<b>A. Grounds, Building, &amp; Small Equipment</b>			
1. Approach & Outlet Channels			
a. Outlet Structure	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
b. Levee or Riprap	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
2. Check Pond Area	AL BR BL CM ED PB	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>		
3. Station & Grounds Cleanliness			
a. General inspection	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
b. Vermin	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
4. Outside Steps, Gratings	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
5. Buildings & Appurtenant Structures (settlement, cracks, and similar items.)	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
6. Exposed Metal & Wood Paint	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
7. Discharge Chambers	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
a. General inspection	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
b. Flapper Gate	All Stations	<input type="checkbox"/> Acceptable <input type="checkbox"/> Unacceptable	
c. Vent Pipe			
8. Guard Chains and			
9. Roof Ventilators			
10. Louvers, motor op			
11. Key interlocks (M			
12. Lubricants on Har			
13. Operations & Main			
14. Furns available fo			
15. Drains, general co			

EXHIBIT-G


**ELECTRICAL AND MECHANICAL MAINTENANCE OF FLOOD CONTROL ANNUAL TESTING REQUIREMENTS**

Pumping Station: \_\_\_\_\_ Date: \_\_\_\_\_ Company: \_\_\_\_\_ Signature: \_\_\_\_\_

Testing Preparation		
	Date Completed and Name	Remarks
1.1		
1.2		
1.3		
1.4		
1.5		
1.6		
1.7		
1.8		
1.9		
1.10		
1.11		
1.12		
1.13		
1.14		

Exhibit C

Page 1 of 9



# 6 **LOOKING FORWARD**

---




# **Water Resources Reform and Development Act of 2014**

- **Nationwide Inventory**
- **Hazard Classification based on Risk**
- **Levee Safety**
- **Public Awareness**
- **Grant Funds**

# Levee Safety Initiative Implementation involves the Levee Sponsor and all of us....



**US Army Corps  
of Engineers®**





# Questions?

