

#### Greenhorne & O'Mara



Indian Creek Watershed (Cobbs Creek) Habitat Improvement By Salman Babar & Alex Haptemariam, P.E., CFM











#### **Project Location**







### **Watershed Characterization**

- Watershed is located in Southern Montgomery County & Western section of the City of Philadelphia along the eastern edge of Piedmont Physiographic province and is characterized by gently rolling to hilly topography.
- The total watershed area is 3.4 sq. miles.
- The upper portion of the watershed is characterized by hilly to steep topography with slopes ranging from 3% to 15%.
- Channel gradient varies from 1.4% to 3%.

















### **Background:**

- 20% of Cobbs Creek watershed is serviced by combined sewers.
- City of Philadelphia has 38 regulator structures within the watershed.
- CSO discharges are the major source of fecal coliform in Cobbs Creek Watershed.





















### **Objective:**

- Reduce and eliminate point source discharge
- Improve the Creeks water quality and reducing local overflow
- Stream bed and bank stabilization
- Wetland and habitat creation
- Elimination of debris accumulation





### **Problems & Issues**

- Current conditions along East & West branch are characterized as very unstable.
- Sediment transport issues at downstream
- Stream bank erosion, lateral migration, channel blockages and stream bed aggradation & degradation are common throughout.
- CSO intake headwall clogging issues
- Accumulated sediment at CSO intake headwall
- Severe erosion at Haverford Avenue bridge











#### **Debris accumulation**



Intake head-wall of culvert (2000)











#### **Accumulated sediment**



Intake head-wall of culvert (2006) Note opening is completely blocked by debris and accumulated sediment











#### Damages



Severe erosion at Haverford Avenue Bridge caused by August 1, 2004 storm





### **Urban Stream Restoration Challenges:**

- Typically requires much greater degree of hydrologic & hydraulic analysis
- Sediment transport studies
- Bankfull indicator challenges
- Reduce base flow
- Increased flood flow
- Reduced Time of Concentration (Tc)











# **CSO Challenges:**

- Infrastructure:
- a) Aged Pipes
- b) Aged Manholes
- c) Existing infrastructure information
- Maintenance:
- 4 chamber manhole
- Fire hydrant
- Manhole at upstream end of 6'x6' box culvert
- Access manholes





### **Methods of Data Collection**

- Existing data was collected, compiled and reviewed.
- Modeling and field studies were conducted to evaluate the current conditions along East & West branch.
- The data collected was utilized to determine structure type, size and location.
- Restoration and management recommendations, design concepts as well as preliminary cost estimates for restoration and management strategies were developed.
- The study included identification of significant plants and plantation of trees, HTRW studies and CSO inspection report









### **Achievements:**

- <u>Volume reduction:</u>
- An average annual volume reduction from 2.9 to 1.2 million gallons (58% reduction) from regulator C\_05
- <u>CSO frequency reduction:</u>
- An average annual reduction in CSO frequency reduction from 17 to 13 overflows per year from regulator C\_05
- Pollutants removal
- <u>Cost effective & Environment friendly:</u>
- CSO reductions were achieved without the construction of new storage facilities
- <u>Replaced aged infrastructure:</u>
- New manhole C-1 and wellhole W-1











## Hydrology

24-hour Peak Discharge				
Storm Event	East Branch	West Branch		
Design Flow	802 CFS	297 CFS		
1.5-YR	1080 CFS	350 CFS		
2-YR	1350 CFS	450 CFS		
10-YR	2430 CFS	850 CFS		
50-YR	3390 CFS	1300 CFS		
100-YR	3610 CFS	1500 CFS		





## Hydrology (cont..)

- Bankfull discharge estimates: Three methods were used to estimate the bankfull discharge
- **1**. Regional regressions developed for use in urban watershed.
- 2. USGS regional regressions
- 3. Hydrologic model output provided by PWD
- 4. Manning's equation and field data









### Hydrology (cont..)

Bankfull Discharge Estimates (West branch)					
Method	1-YR (cfs)	Bankfull (cfs)	2-YR (cfs)		
<b>Regional Regression</b>	ND	296	ND		
USGS	ND	ND	416		
PWD	98	ND	450		
Manning's Equation	ND	297.3	ND		

Bankfull Discharge Estimates (East branch)					
Method	1-YR (cfs)	Bankfull (cfs)	2-YR (cfs)		
Regional Regression	ND	294	ND		
USGS	ND	ND	408		
PWD	365	ND	1350		
Manning's Equation	ND	296	ND		







### **Bankfull Channel Geometry Comparision**

Reach ID		.*	
(Drainage Area)	Cross-sectional Area	Width	Depth
Data Source	(ft <sup>2</sup> )	(ft)	(ft)
West Branch		1	
(1.71)	58.4	27.1	2.18
Regional Regression			
West Branch	57.1	36.6	1.65
Measured	(55.0 - 59.1)	(25.4 – 48.1)	(1.1 – 2.3)
Upper East Branch		1	
(1.7)	58.2	27.0	2.17
Regional Regression			
Upper East Branch	59.3	31.6	1.9
Measured	(58.9 - 60.1)	(27.5 - 34.1)	(1.8 – 2.2)
Lower East Branch			
(3.41)	94.5	38.3	2.54
Regional Regression			
Lower East Branch	98.6	40.8	2.5
Measured	(94.5 – 102.3)	(35.7 – 45.9)	(2.1 – 2.9)

Table 5 – Indian Creek Bankfull Channel Geometry Comparison of Predicted Values to Field Data







### **Classification Summary Table**

Reach	Width (ft)	Bankfull Mean Depth (ft)	Bankfull XS Area (ft <sup>2</sup> )	Width/Depth Ratio	Entrenchment Ratio	Slope (ft/ft)	D50 (mm)	Stream Type
West Branch 1	48.1	1.1	55.0	42	2.1	0.021	39	C4
West Branch 2	37.5	1.5	55.6	25.3	2.9	0.021	39	D4
West Branch 3	35.2	1.7	58.7	21.1	1.6	0.01	39	B4c
West Branch 4	25.4	2.3	59.1	10.9	5.2	0.01	39	E4
Upper East Branch 1	32.4	1.8	58.9	17.9	1.85	0.01	76	B3c
Upper East Branch 2	32.5	1.8	58.3	18.1	1.4	0.01	76	F3
Lower East Branch	45.9	2.1	94.9	22.2	1.1	0.01	76	F3

Table 6 – Indian Creek Reach Classification Summary Table





### **Hydraulic Analysis**

- Analyze existing water surface elevations, channel velocities and other pertinent hydraulic parameters associated with the channel.
- US Army Corps of Engineers Hec-RAS computer modeling program was used to perform hydraulic analysis.





### **Functions of In-stream Structures**

- Maintain stable W/D ratio
- Maintain necessary shear stress to move large particles
- Decrease near bank velocity, shear stress or stream power
- Ensure stability of structure during high flows (floods)
- Maintain fish passage at all flows
- Improves fish habitat and fish spawning
- Visibly compatible with natural channels
- Less costly than traditional structures





### **Considerations for In-stream structures**

- Rock size is based on bankfull shear stress and stream size
- Footers are used in absence of bedrock
- Location of these structures is finalized after proper design of dimension, pattern and profile for the restored channel





### **Types of In-stream structures used**

- Cross vanes
- Rock vanes
- J-hook vanes:
- Imbricated riprap wall
- Step pools









#### **Instream Structure Details**













#### **Instream Structure Details**











#### **Under cutting in West branch**













### **Eroding banks**



Eroding bank, exposed manhole, old support columns along upstream end of Reach 1





### **Stormdrain relocation**

- To ensure natural design
- Taking out hardened infrastructure such as RCP and headwall
- 18" RCP exposed along West branch will be reconstructed and relocated.



























































### **Bankfull benches**













#### **Bankfull benches**













#### **East branch**







































Boulders dumped over slope to repair gully erosion along Reach 1













#### **EAST BRANCH GULLY NO. 4 PROFILE**

**SEE PLAN SHEET 8** 

Scale: 1"=10' (V) 1"=10' (H)



























### **Routing between sewer interceptor & regulator:**





### **Representation of drainage connection to Interceptor**







### **CSO Design**

- CSO design includes a weir wall with 24" orifice inside concrete vault structure.
- The 24" orifice is used to divert the flow from the vault into the existing sewer interceptor.
- The 24" orifice size was selected to reduce the likelihood of clogging.
- The existing 700LF of underground reinforced concrete box (RCB) serves as storage during large storm events.
- The downstream portion of the existing reinforced concrete box (RCB) will be removed.















#### **Connection between regulator & overflow**





#### **Connection between Interceptor and regulator**











#### **CSO regulating chamber V-1 details**





#### **CSO regulating chamber C-1 details**













#### **Connection details**



# **Thank You!**

