

**Case Studies of Floodplain** and Stream Restoration (FSR) Projects and their Potential Use for Flood Hazard Mitigation and **Community Resiliency** 

Presented by: Rich Pfingsten, PWS Stantec Consulting Services Inc.

November 8, 2018



### Goals & Objectives

- FSR for Hazard Mitigation and Community Resiliency
- Review of Basic Geomorphic Principles
- Natural Channel Design Overview
- Design of Vane Structures
- Design of Floodplain and Habitat Features
- Case Studies of Floodplain and Stream Restoration (FSR) Projects





FSR for Hazard Mitigation & Community Resiliency

#### FSR for Hazard Mitigation

- Hazard Mitigation is any action taken to reduce or eliminate longterm risk to life and property from a hazard event.
- FEMA encourages communities to incorporate methods to mitigate impacts of climate change into eligible Hazard Mitigation Assistance (HMA) funded risk reduction activities.
- FSR projects are designed to be self-sustaining and are eligible for HMA funding to mitigate for:
  - Erosion
  - Flood Risk
  - Flood Reduction
  - Drought Mitigation



#### FSR for Community Resilience

- Community Resiliency is defined as the ability of a community to:
  - Adapt to Changing Conditions including Climate Change
  - Withstand Disruption
  - Recover from Emergencies
- FSR projects have the capacity to provide resilience to threats and hazards to multiple Ecosystem and Natural Resource issues:
  - Water/Hydrological Systems
  - Fisheries
  - Agriculture (Production & Livestock)
  - Wildlife Ecosystems
- FSR projects also address threats and hazards caused by or exacerbated by Climate Change including:
  - Climate Change Adaptation & Mitigation
  - Changing Weather Patterns & Severe Weather
  - Droughts and Floods



#### Fluvial Geomorphology


Branch of science concerned with influence of rivers and streams on the formation of the earth's surface

**Governing Processes:** 

- Erosion
- Sediment Transport
- Sediment Deposition




#### Natural Stream Systems





#### **Entrenched Channel**





#### Bankfull Discharge

- Controls Channel Form
- Corresponds to the Discharge at Which Channel Maintenance is Most Effective
  - Recurrence Interval on Order of 1.2 to 1.6 Years
- Higher Recurrence
  Interval in Urban
  Watersheds



#### Bankfull Indicators

Flat, Depositional Surface Adjacent to Active Channel

Height of Depositional Features (Point Bars)

Change in Vegetation

Slope or Topographic Breaks or Changes Along the Bank



### Past Attempts at Designing Streams to Prevent Flooding





#### Past Attempts at Designing Streams to Prevent Flooding





#### Past Attempts at Designing Streams to Prevent Flooding





#### Designing Channels to be Natural and Resilient





#### Designing Channels to be Natural and Resilient





#### Differences

#### CONCEPT TRADITIONAL GEOMORPHOLOGICAL

Time Short-term Model Theoretical Clear Water Spatial Scale Reach Boundary Rigid Maintenance High Design Flow 100 yr. Factor of Safety Conservative Long-term Field Measurement Sediment Laden Watershed Mobile Sustainable Bankfull Flow Balance of Forces



# **River Stability Definition**

River stability (equilibrium or quasi-equilibrium) is defined as "the ability of a river, over time, in the present climate to transport the flows and sediment produced by it's watershed in such a manner that the stream maintains its dimension, pattern and profile without either aggrading or degrading" (Rosgen, 1994, 1996, 2001)





# Indicators of Instability


- Incision/Bedcutting
- Channel Filling
- Entrenchment/High Streambanks
- Lateral Migration
- Over Widening
- Lack of Habitat
- Eroded Banks
- Slope Instability





# Simon's Modification of Schumm's Model


Class I. Sinuous, Premodified h<hc



Class II. Channelized h<hc floodplain


h

Class III. Degradation h<h₀





Class IV. Degradation and Widening h>hc

terrace



Class V. Aggradation and Widening h>hc







### Natural Channel Design

Process by which new or re-constructed stream channels and their associated floodplain riparian systems are designed to be naturally functional, stable, healthy, productive, resilient to changing conditions, and sustainable.






#### Phases of Natural Channel Design Using a Geomorphic Approach

- 1. Define Restoration Objectives
- 2. Develop Regional & Localized Specific Geomorphic and Hydraulic Data
- 3. Conduct Watershed/River Assessment
- 4. Assess Potential for Passive Restoration (i.e. Land Use Changes)
- 5. Initiate Natural Channel Design w/ Analytical Testing of Hydraulics & Sediment Transport
- 6. Design Stabilization/Enhancement Measures to be Resilient
- 7. Implement Proposed Design
- 8. Design & Implement Monitoring & Maintenance Plan



#### Natural Channel Design Process

- Determine Site Constraints
  & Design Parameters
- Determine/Design Impact of Flood Flows on Potential Design
- Predict Stable Geometry
  Based on Reference Reach
- Check Sediment Transport Competency and Capacity
- Iterative Design Until Geometry and Calculated Depths Converge





# Primary Reference

Chapter 11: Geomorphic Approach for Natural Channel Design

**USDA NRCS**, Stream Restoration Design Handbook, 2007.

#### Stream Restoration Design

National Engineering Handbook Part 654 Released, August 2007 (vs. 031908)

U.S. Department of Agriculture

Natural Resources Conservation Service



# Types of Restoration

- Priority I Raise the Stream up to the Floodplain
- Priority II Bring the Floodplain Down to the Channel
- Priority III Do Not Alter
  Planform but Change
  Stream Type Along Existing
  Pattern
- Priority IV Armour in Place using Soil Bioengineering or More Structural Approaches







#### Reduction of Flood Elevation


- Priority II or III Potential to Reduce Flood Elevation
- Priority II Excavate
  Floodplain, Creating
  Storage
- Priority III Do not Alter Planform but Alter Cross Section, which Often Lowers Flood Elevation
- Comparing Flood
  Elevations of Same
  Precipitation Event






Natural Channel Design Overview

#### **Reduction of Flood Elevation**



Degraded or Channelized Stream






# Use of Structures in Natural Channel Design

- Provide Grade Control
- Maintain Stable Aquatic Habitat
- Maintain Shear Stresses for Sediment Transport
- Decrease Bank Erosion
- Fish Passage at All Flows
- Control During Larger Flows
- Diversion Structures
- Bridge Openings






#### **Boulder Vane Riffle**






#### Rock and Roll Riffle






#### Constructed Riffle












#### Log Vane with Sill



#### Design of Floodplain & Habitat Features

#### Wood Toe



#### Design of Floodplain & Habitat Features Woody Toe Sod Mats



## Woody Toe Sod Mats














## Vernal or Ephemeral Pools












## **Design Considerations**

Hydrology Depth – Deep - Shallow Vegetation – In-pool - Shading Outlet Cut/Fill Balance





## Functions and Linkages

#### Habitat

- Amphibians
- Invertebrates
- Breeding
- Rearing
- Refuge
- Nutrient Processing
  - Organic Inputs
  - Hydric Soils

Ecosystem Functions Flood Storage (Oxbows)







# Back Creek Stream Restoration at Lithia Road, Troutville, VA (VDOT)




Pre-Restoration Conditions

- Aggrading Channel as a Result of:
  - Upstream Watershed Conditions
  - o Poor Restoration Attempt
- Serious Flooding During Most Rain Events
- Major Road for Area
- Impassable 5X Per Year



# Back Creek Stream Restoration at Lithia Road, Troutville, VA (VDOT)



Restoration Design & Construction

- Proper Assessment of Geomorphic Conditions
- Natural Channel Design Approach
- Fish Habitat
  Improvement
- Improved Flood Conveyance



#### Case Studies of Floodplain and Stream Restoration Projects Dare Elementary School Stream Restoration, York County, VA



#### Pre-Restoration Conditions

- Large Source of Erosion to
  Downstream Watershed
- Water Quality Problems

Pre-Restoration Conditions

- Collapsing Concrete-Lined
  Channel 20' Headcut
- 800 Linear Feet of Channel
- Safety Issue to Adjacent Properties



#### Case Studies of Floodplain and Stream Restoration Projects Dare Elementary School Stream Restoration, York County, VA




#### Restoration Design & Construction

- Priority III Restoration Approach
- Designed In-Line BMP Upstream to Provide Peak Flow Attenuation & WQ Treatment
- Stabilized Severe Headcut
- Protected Adjacent Properties
- Maintained Low Flow Channel Connected to Floodplain
- Phosphorus Removed 141 LB/YR
- Savings Per LB of TP \$8,511
- Value to Watershed \$2.4M
  - Total Project Cost \$1.2M



### Dare Elementary School Stream Restoration, York County, VA



### Dare Elementary School Stream Restoration, York County, VA



Post-Construction Conditions

 Project Stable and Functioning as Designed for 5 Years






Middle Fork of Beargrass Creek at Cherokee Park Stream Restoration, Louisville, KY

































## **QUESTIONS?**

#### November 8, 2018

Presented by:

Rich Pfingsten, PWS <u>Rich.Pfingsten@stantec.com</u>

